



Achtung: Gültig für die Serienausführung mit beidseitigen Auffahrklappen.  
 Anstelle des Leitungskanals kann auch ein Leerrohr DN100 verlegt werden.  
 Bauseits am Bedienaggregat bereitstellen: 3PH.N+PE, 400V, 50Hz  
 Absicherung 16A träge  
 Wasserabfluss in der Vertiefung empfohlen.

Valid for inground version. Lift with ramps at each end.  
 By customer: 3PH.N+PE, 400V, 50Hz (observe the power supply of your country)  
 fuse 16 Ampere time lag  
 We recommend a wateroutlet in the pit.

Die Position des Bedienaggregates kann den örtlichen Gegebenheiten angepasst werden. Ggf. sind die Versorgungsleitungen anzupassen.

Wir weisen in unseren Plänen auf die Mindestanforderung des Fundamentes hin, jedoch der Zustand der örtlichen Gegebenheiten (z.B. Untergrund) obliegt nicht unserer Verantwortung. Im Bedarfsfall ist ein Architekt, Statiker hinzuzuziehen.

We point out the minimum requirement of the foundation in our plans. The condition of the local realities (for example: ground under the foundation) does not lie our responsibility. If necessary an architect must be consulted.

The Position of operating unit can be changed. If necessary the feeding lines must become extended.

Änderungen vorbehalten/ Subject to alterations!

UNI-LIFT 5000 CLT/NT Plus	
Schiene bodeneben Radfreiheber steht über Schielenlänge 5000mm	rail flush with floor wheel free lift over the floor rail 5000mm long

**Nussbaum**  
 www.nussbaum-lifts.de

13.03.02//M.G.	6008_EINBAU
----------------	-------------